SLBP Proj. No. 9148-0028 Bridge No. 148-028

LOCAL INLAND WETLAND MEETING

REHABILITATION OF THE SOUTH TURNPIKE BRIDGE OVER MANSION ROAD BROOK WALLINGFORD, CONNECTICUT January 6, 2021







EXISTING CULVERT OVERVIEW

•Structure Type

Twin Concrete Box Culverts 4'X3' (Constructed 1935) Total width (out-to-out) of 39 feet No Skew Concrete endwalls •*Report dated January 2018* Structure Evaluation = Poor Condition •*Hydraulically Inadequate* •ADT = 7,417 (Traffic Counts 2016) •Numbered FEMA Flood Zone AE •Less than 1 SQ. MI. Drainage Area



LOOKING NORTH OVER BRIDGE





LOOKING SOUTH OVER BRIDGE





EXISTING BRIDGE ELEVATIONS

Upstream Face



Downstream Face







Spalled Downstream Wingwall



Spalling Inside Box Culvert





FEMA FLOOD INSURANCE RATE MAP

FEMA Elevations

■ Upstream approx. 30.7'



BRIDGE NO. 148-028





PROPOSED CONSTRUCTION

- Divert flow from one culvert to next with the use of temporary cofferdams to perform work in the dry
- Reconstruct and repair existing headwalls and wingwalls
- Clean culverts
- Install centrifugally cementitious lining
- Improve inlet with beveled edges
- Install large boulders top dressed with standard riprap directly adjacent to outlet



WETLAND/WATERCOURSE IMPACTS

Watercourse Impacts		Wetland Impacts		
Temporary	Permanent	Temporary	Permanent	
724 S.F.	1348 S.F.	975 S.F.	630 S.F.	
Total = 2,072 S.F.		Total = 1,605 S.F.		

Overall Total Impacts = 3,677 S.F.



RDINARY HIGH WATER (OHW MPORARY WATERCOURSE IMPACTS

MANENT WATERCOURSE IMPACTS EMPORARY WETLAND IMPACTS

RMANENT WETLAND IMPACTS

ANENT UPLAND IMPACTS

EMPORARY UPLAND IMPACTS



2

















WMC

CONSULTING ENGINEERS





HYDRAULICS AND HYDROLOGY

Table 1: FIS Flow Rates

Return Frequency (Years)	Flow Rate (CFS)
10	115
50	215
100	330
500	660

Table 5: Comparison, 100-Year Regulatory Flood Event², Existing versus Proposed, Encroached & Unencroached Condition Elevations

		CWSEL								
		Encroached			Unencroached					
		(1)	(2)	(2)-(1)	(3)	(4)	(4)-(3)			
Section ID ¹	FIS ID	Existing	Proposed	Δ (FT)	Existing	Proposed	Δ (FT)			
875	F	30.34	30.32	- 0.02	30.16	30.33	0.17			
860	Е	30.34	30.32	- 0.02	30.16	30.33	0.17			
8451		30.32	30.30	- 0.02	30.16	30.33	0.17			
666	D	30.29	30.27	- 0.02	30.12	30.30	0.18			
650	Sou	th Turnpike Road Culvert								
625	C	22.89	22.89	0.00	22.90	22.90	0.00			
340	В	22.08	22.08	0.00	22.07	22.07	0.00			

1. Sections added for HEC-RAS - not in effective model

2. Regulatory model with alternate starting WSEL

HYDRAULIC INFORMATION

Drainage Area: 0.94 mi²
Design Storm Frequency: 100 year

Does not meet freeboard (1-ft)

Design Discharge:

FIS Flow Rate: 330 cfs
FEMA: Flood Zone AE (Regulatory Floodway Established)

Flow:

Average Daily Flow: 2 cfs
Average Spring Flow: 3 cfs









ENVIRONMENTAL CONSIDERATIONS

& ANTICIPATED PERMITS

- Best management practices will be used to handle sedimentation control
- Inland wetlands/regulated area impacts will be kept to a minimum
- Any unconfined in-stream work within the Mansion Road Brook should be restricted to the period from June 1 to September 30, inclusive
- Disturbed areas during construction will be restored upon completion
- Permits required:

ACOE – Pre-Construction Notification (PCN) DEEP 401 Water Quality Town IWWC Town Flood Management Certification



<u>PROJECT COST</u>

- The cost of construction for the year 2021 is approximately \$525,000
- Funding will be 50% State funds and 50% Town funds
 - State: \$262,000
 - Town: \$262,000



- Start/End of construction: June 1– September 30
- Duration of construction: Approx. 4 months



CONTACT INFORMATION

Town of Wallingford

Alison Kapushinski *Town Engineer* 45 South Main Street *Wallingford*, CT 06492 203-294-2035

Town of Wallingford

Robert V. Baltramaitis Director of Public Works 29 Town Farm Road Wallingford, CT 06492 203-294-2105

WMC Consulting Engineers (Designer)

Keegan Elder, P.E. Project Manager 87 Holmes Road Newington, CT 06111 kelder@wmcengineers.com 860-667-9624

